

Modular Construction

Team Members:

Derry Radityatama | Kenichiro Suzuki |
Lin Shi | Ning Wang | Wenjun Gao

Instructors:

Prof. Feniosky Peña-Mora | Prof. Rick Bell

Presentation Date: Mar 23, 2022



Outline



01

Relocatable Modular Buildings

Background / Problem / Case Study

02

Reversible Building Design

Concept / Case Study / Challenge

03

Construction Material - Reversible & Relocatable Building

04

Case Study - Reversible & Relocatable Building

05

Cost Estimation of Modular Construction

01

RELOCATABLE MODULAR BUILDINGS



Definition and Background

Problems

Case studies

Solutions

Definition

Modular Construction

Process in which a building is constructed off-site, under controlled plant conditions, then assembled on location.

Modular Construction Institute: <https://www.modular.org/>

- **Permanent Modular Construction**
- **Relocatable Modular Construction**

"Relocatable buildings are defined in the International Existing Building Code as partially or completely assembled buildings constructed and designed to be reused multiple times and transported to different building sites."

2020 Relocatable Modular Construction:

<https://growthzonesitesprod.azureedge.net/wp-content/uploads/sites/2452/2021/08/MBI-RB-annual-report-2020-FOR-DIGITAL.pdf>

Definition

Comparison of Permanent Modular Construction (PMC) and Relocatable Buildings (RB)

	Permanent Modular Construction (PMC)	Relocatable Building(RB)
Manufacturing Ratio/Rate of Recycling	60-70%/74%	80-90%/100%
Field Construction	Vertical installation piping, boilers, balcony ceilings, wall for evacuation, welding and bolt joints between modules, fireproofing, and exterior finish.	Electrical/equipment piping connections, bolt joints between modules
Exterior Finish	Installation of temporary scaffolding, exterior finish work	No external finishing work
Foundation	Non-recyclable	Recyclable
Elevator	Site construction	Elevator modularization
Junction between modules	Bolting, welding, wet work	Bolting, dry work
Waterproof	Breathable waterproofing paper on site	Units individually waterproofed
Usability	Permanent residence	Can be moved and reinstalled in another location

Trend

Due to megatrends such as urbanization and ageing of the population, different types of regions are facing different types of demographic challenge.


- Fast-paced demographic change
- Put a lot of pressure on the environment

Relocatable Modular Building offer one potential solution

Background


Embodying circularity through usable relocatable modular buildings

<https://www.proquest.com/docview/2173504215?accountid=10226&parentSessionId=v2uBhINlm4%2FVIRId3QXmMsg9%2B56%2F3Cg9NH9XLsd6F8Q%3D&pq-origsite=summon>



Population growth (annual %, 2015)

<https://www.populationpyramid.net/hnp/population-growth/2015/>



Factfulness, Straight Line Instinct & World Population

<https://www.athoughtabroad.com/2020/04/19/factfulness-straight-line-instinct-world-population>

Problems



Disassemble



Transportation

- road and/or sea transportation
- every time building relocate



Design

- dimensional restrictions
- aesthetic quality



Regulation

- different laws and systems across states and countries
- ownership

Case studies



Wing Aviation, LLC - Christiansburg NEST (First Place)
Built by BMarko Structures, LLC.



Cole Starnes Abbotsford Temporary Housing Facility
Built by Metric Modular.




Residence Modular Hotel for winter Olympic
Built by POSCO A&C.

Solutions




Disassemble



Reversible Building Design




Transportation



Use already existing standards




Design



Create a new size standard



Regulation



Establish common regulations



02

REVERSIBLE BUILDING DESIGN

Concept

Case Studies

Challenges



Co-funded by the Horizon 2020
Framework Programme
of the European Union



BUILDINGS AS MATERIALS BANKS

The influence of BAMB in shaping circularity
the construction industry

- Starting date: 1st of September 2015
- 16 partners from 8 European countries

Caroline Henrotay - Brussels Environment




UNIVERSITEIT TWENTE




Materials Value in Commodities Markets vs. Buildings

In Commodities Markets




For Building Owners

Reversible Building Design Framework




REUSE %


■ irreversible ■ partly reversible ■ reversible




1 Fixed structure



2 Partly reversible



3 Reversible structure



IRREVERSIBLE


- $RP < 0.3$
- End of life options = RECYCLING/DOWN CYCLING.

PARTLY REVERSIBLE


- $0.2 < RP < 0.6$
- End of life options = REPAIR, DIRECT REUSE, REMANUFACTURING.

REVERSIBLE

- $RP > 0.6$
- DIRECT REUSE AND REPAIR of its parts the system can be RECONFIGURED AND UPGRADED



Design Task is to guaranty
long term value of buildings by **high transformation** and
reuse potential of buildings and materials on three levels



Reuse potential
+
Transformation
potential
=
Reversible buildings


Demolition = Design Mistake

THREE DESIGN DIMENSIONS OF REVERSIBLE BUILDINGS

Elma Durmisevic, University of Twente



Reversibility of space
Adapt space



Reversibility of structure/
**Reconfigure /upgrade
structure**



Reversibility of material/
**Separate elements/
material**

REVERSIBLE BUILDING DESIGN



Technical Reversibility

Spatial Reversibility



Reconfigure structure

Separate materials



Adapt space

©Model of Durmisevic

Spatial Reversibility

- Dimension (Building Level)
- Position of Core Elements
- Building Level Disassembly
- Capacity of the core





Figure 13: Building reconfiguration

Dimensions
Functional interdependence
Position of core elements



Scenario thinking

- Technical services
- Unit separations
- Internal partition
- Envelop







Figure 14: Spatial reversibility


Technical Reversibility

- Functional decomposition
- Systematisation and clustering
- Hierarchical relations between elements
- Base element specification
- Assembly sequences
- Interface geometry
- Type of the connections
- Life cycle co-ordination in assembly/disassembly





- Red representing more permanent part
- Green representing variable/ exchangeable parts of the structure
- Blue representing intermediary between the permanent and variable parts of the structure
- Gray represent replaceable infill elements





CASE STUDIES: Circular Retrofit Lab



Type	Refurbishment, integration of transformed elements
Size	size: 180 m ²
Function	Exhibition and office space
Location	VUB Campus, Brussels, Belgium



circular product
(service) systems




General aims

A catalyst for circular renovation

Demonstrator for reversible building principles


Collaborate with industry and test case for circular business models

Exemplary for other circular renovation experiments




internal transformation


prototyping
€60.000




external transformation




module reconfiguration



dissemination space
public



temporary plugin offices
non-residential




eco guestrooms
residential




INTERNAL TRANSFORMATION


WORKING GROUP INTERNAL SOLUTIONS




Type 1



Type 2




Type 3



Type 4

EXTERNAL TRANSFORMATION

DEVELOPMENT PRE-ASSEMBLED FACADE COMPONENTS



STAKEHOLDERS - PARTNERSHIPS

STEERING GROUP



KADERSTUDIO



MK Engineering

WORKING GROUP INTERNAL SOLUTIONS

■ GEBERIT



WORKING GROUP BUILDING SERVICES

MK Engineering

■ GEBERIT

zehnder

■ bao



WORKING GROUP FACADE SOLUTIONS






Jonckheere Projects
building a future in wood today


SAINT-GOBAIN
GLASS

ISOVER
SAINT-GOBAIN



Reversible connections with reusable components





wooden frame



gypsum fibre board



electricity



screws / clips



cardboard frame




gypsum plasterboard



in situ



tape



THE CHOICE OF THE INTERNAL STRATEGY

TYPE 1 HIGHER RATE OF CHANGE

LOCATION: dissemination room (ground floor) and offices (1st floor)

CRITERIA:

- (Dis)assembled in a short time
- Reusable building components
- Reversible connection techniques
- Allow multiple (dis)assemblies

Flexible space



TYPE 2 HIGH TECHNICAL FLEXIBILITY

LOCATION: technical walls to adjust, adapt, repair and maintain the technical services that are behind, the finishing panels/plinths


CRITERIA:

- Allow multiple reuse
- Allow multiple (dis)assemblies
- Preserve good acoustic properties


GIS prototype wall



TYPE 1 HIGHER RATE OF CHANGE



TYPE 2 HIGH TECHNICAL FLEXIBILITY




TYPE 3 LOWER RATE OF CHANGE

LOCATION: The partition walls between the two eco-guestrooms

CRITERIA:

- Comply with acoustic standards
- Comply with fire safety regulation
- Flexible integration of technical functions

- Saint-Gobain Dry-wall (fire rated)
- BAO Living prefab module



FIRST FLOOR



GYPROC SAINT-GOBAIN FIRE SAFETY


TYPE 4 LOW RATE OF CHANGE

LOCATION: The closed south facade and wall surfaces under the windows

CRITERIA:

- a low environmental life cycle impact
- reuse of components at the end of functional life


- Saint-Gobain prototype wall




GROUND FLOOR (AND THE FIRST FLOOR)




GYPROC SAINT-GOBAIN CIRCULAR PROTOTYPE



TYPE 3 INTERMEDIATE RATE OF CHANGE



TYPE 4 LOW RATE OF CHANGE



TYPE 4 LOW RATE OF CHANGE

Conclusion: Circular Retrofit Lab

- Pioneers' work
- Eco system per individual company needs to be defined for circular economy
- Design and engineering tasks for development of Transformable / reversible buildings are very intensive and cost much more time than design of traditional “linear” buildings. Standardisation of design process is needed
- Realization of transformable building requires different approaches to each segment of the building. This requires lot of new product development in the future.
- Industry is more and more aware of the need to change
- Need for business cases
- Experiments - scaling opportunities



03

Durability

Durability challenge of relocatable and reversible buildings

Current solutions for corrosion prevention

Novel Construction Material

Benefits

01 Durability challenge of relocatable and reversible buildings


- With the emerging technology of modular construction especially for relocatable buildings and reversible buildings, we could realize locating our modular units in different regions and reusing them multiple times.
- Besides regular locations of application, relocatable & reversible building plays an irreplaceable role in emergency/post disaster relief areas and other swing space. And reversible design of building achieves recycled 60%-90% building materials. The most significant feature is that it could be directly used or reconstructed in extreme environments, such as snow & ice regions, tropical rain forests and marine locations.



Tropical Rain forests



Snow & Ice regions




Marine locations

01 Durability challenge of relocatable and reversible buildings



Steel Corrosion

- Freeze–thaw cycle, Carbonation and Chloride ion attack, would accelerate the steel corrosion process and have a negative impact on buildings' durability and cut down their service life significantly.
- Modular constructions mainly consist of steel which accounts for 60%-70% of total components. The excessive proportion of steel would induce high sensibility of corrosion causing substantive maintenance cost and inevitable negative impact on durability of modular buildings.



Overly Cost

- Total direct cost of corrosion in the United States is approximately \$276 billion per year, which is 3.1% of the nation's gross domestic product (GDP). Construction and infrastructure industry accounts for 18.1% with \$50 billion per year [1].
- Preventing the corrosion of steel in concrete structures subjected to various extreme environments are urgent problems to be solved.

01 Durability challenge of relocatable and reversible buildings

Category	Relocatable buildings' Service life	Permanent / Traditional buildings' Service life
Foundations	50 years	50 years
Building structure	10-15 years	50+ years
Interior finishes	5-10 years	5-10 years
Roofing systems	20 years	20 years
Mechanical systems	20 years	20 years
Electrical and plumbing systems	25 years	25 years


- Relocatable buildings have an average service life of up to 10-15 years [2]. Comparing to permanent or traditional constructions which have 50+ years service life, relocatable buildings have a below-average service life because of steel corrosion effect under its changing use circumstances including snow regions, tropical rainforest and marine locations [3].
- Short service life hinder the development and wide application of modular construction. Therefore, it is reasonable to find a way enhancing its capability of corrosion resistance and extending its service life.
- The reversible design of modular construction has similar problems and situations. Both the reuse environment and deconstruction process will have a negative influence on the service life of its components. In other words, reversible design could be meaningful only when the service life of the building is prolonged and then recycling more building materials can be realized.

02 Current solutions for corrosion prevention



Metal Plating

- Electroplating
- Electroless
- Hot dipping




Corrosion inhibitors

Corrosion inhibitors are chemicals applied to the surface of the metal that react with the metal or the surrounding gases to inhibit or suppress the electrochemical processes that lead to corrosion.




Sacrificial coatings

A coat of a metal that is likely to oxidize is added on the surface of the metal you want to protect.



Metal Plating



By controlling the environment, we can prevent or reduce the rate of corrosion. Reduce exposure to moisture while complex alternatives include controlling the oxygen, sulfur, or chlorine levels in the environment around the metal.



Modifying the design / Using stainless steels

Adding Nickel or other rare metal into the steel processing progress.

02 Current solutions for corrosion prevention



Carbon steel & Stainless Steel

- Traditional methods greatly increase the cost of construction because of expensive protective materials. For instance, using stainless steel, comparing to the carbon steel, stainless steel has a much higher selling price, which is about 3-4 times as expensive as carbon steel on average.
- As a rare metal and main component of stainless steel, nickel is a derivative financial investment tool, and its market price fluctuation is greatly affected by the financial market. With the risk of today's geopolitics, the supply of Nickel decreased dramatically, and the market price skyrocketed.
- The current market price of nickel (stainless steel) is nearly 11 times of HRC (carbon steel) and the gap between them is likely to widen further because of geopolitical factors.
- Current solutions of steel corrosion prevention could not meet the demand of a cheap and effective method in order to enhance the durability of modular buildings.

03 Novel Construction Material - TDA

- **Steel protective coating**

A fresh coat of **TDA (Rubber) paints** will enhance the appearance of the metal structure and prevent corrosion because they act as a barrier that prevents the metal's chemical structure from interacting with environmental compounds like water and oxygen that result in corrosion.

Applying a **rubber powder coat** is another effective method of corrosion prevention. Rubber powder can be obtained by cutting TDA into powder with particle size of 0.180-0.425mm. The powder coat applied on the surface of the metal is heated to form a smooth protective film. For metal sheets, rubber powder coat can also help to prevent corrosion to some extent and also hide imperfection caused by contact with the rollers at the mills.



Mix proportions of rubber concrete (kg/m³).

Rubber concrete	Cement	Sand	Aggregate	Water	Rubber
RC-0	337	506	607	135	0
RC-10		455			37
RC-20		405			74

- **Concrete**


The mix proportions of rubber concrete are listed in Table 1, rubber particles was used to replace 0%, 10% and 20% of sand under the same volume. The rubber particles used in the concrete belong to broken rubber powder, particle size is 1-2 mm.

The low-permeability and cracking-resistance characteristics of rubber demonstrate its potential to delay chloride ion penetration and corrosion-induced cracking from the perspective of material properties. Therefore, the goal to extend the service life of modular units is achieved.

- **Foundation**

Normally half of the foundation is below the surface water level, which is the most vulnerable part to steel corrosion and the most important element affecting the durability of the structure. Same with the second point, in order to enhance the foundation's resistance of steel corrosion, we use rubber concrete to replace traditional vulnerable construction materials.


04 Benefits



04 CASE STUDY

Flying Sales Center

Reversible & Relocatable Modular Building



Poly - The Sky Garden - Modular Detachable Sales Center



- Location: Fujian, China
- Project size: 294 square meter
- Function: Real Estate Sales Center
- Project Background: Adjacent to two arterial roads and surrounded by villages in the city
- Dilemma/Problem of traditional sales center:
 - Temporary Use vs. High Investment
 - Long waiting time
- Owner: Poly Developments and Holdings
- Design Company: HYP-ARCH Design Consultant
- Modular Service Provider: Unitised Green Prefab
- R&D Period: Oct 2017 - Oct 2019
- Fabrication: Start on Oct 5, 2019
- Transportation: Nov 12, 2019
- Onsite Construction: 5 days (Nov 14 - 18, 2019)



Lin



刘其东【优积科技&璞宿文旅】



王宁 nw2480




WenjunGao

Interview with Liu Qidong = CEO of Unitised Green Prefab




优积科技
UNITISED GREEN
PREFAB

Columbia University | CBIPS Research
Modular Construction Group
Mar 20, 2022




LIFT BY CRANE



Lifting and assembly order:

Unit 4 → Unit 3 → Unit 2 → Unit 1 → Unit 5 → Unit 6 → Walkway → Sheet Wall



<https://zhuanlan.zhihu.com/p/98565937>

<https://www.archiscene.net/commercial/poly---futuristic-modular-boxes/>

http://www.uedmagazine.net/ued_content_473_473_13583.html



Unitised Green Prefab - Crowne Plaza Hotel Extension at Singapore Changi Airport (Video)





Unitised Green Prefab - Manufacturing Conditions

- Factory Location
 - Preferred distance between the factory and the site < 300 km
- Productivity
 - Singapore Crowne Plaza Hotel Extension Project - 4 finished modules per day (Shanghai, China | 2016)
 - 8 finished modules per day (Langfang, China | Present)
- Automatic Level
 - Unmanned production of steel structure and some components (Present)
 - Challenge: Full automation requires too much investment

Poly · The Sky Garden - Modular Detachable Sales Center

- Spreader for Lifting




- Module Design & Installation
 - 10 mm Preserved between Modules as Expansion Joint
 - Waterproofing Membrane & Seal Strip Laying in Joints

- Foundation: 25-35mm Thick Plain Concrete Slab + Steel Pile




Poly · The Sky Garden - Modular Detachable Sales Center

- Detach Process



Poly · The Sky Garden - Modular Detachable Sales Center


- Reuse Processes Diagram




Reversible & Relocatable Design Considerations

- ★ Convenience
- ★ Economy
- ★ Maintenance

- Replaceable Outer Cover
 - Look completely new
 - Adaptable to different styles
- 5 mm Seam Reserved between Panels
 - Increase tolerance for dimensional errors
 - Reduce material wear during detachment
- Lightweight and Less Deformable Material with High Assembly Rate
 - Make transportation easier
 - Reduce material loss when reusing



Replace Building Skin



Metal



Glass



Stone, Ceramic,
Concrete Panel



Polycarbonate
Panel



Plywood



Cost Estimation of Modular Construction

05

01 Cost Estimation Process

Step 2 : Selecting work items for fabrication

Determine modularization ratio of each work items according to criteria and objectives

Step 4 : Estimating Fabrication cost

Fabrication cost

$$= W_M \times N_{\frac{MHR}{Ton}}_{for\ Fab.} \times F_{L_{off-site}} \times F_{P_{off-site}} \times AR_{off-site}$$

Step 6 : Estimating Installation cost

Installation cost

$$= W_M \times N_{\frac{MHR}{Ton}}_{Inst.} \times F_{P_{on-site}} \times AR_{on-site}$$

Step 8 : Using Monte-Carlo simulation

Project phase and Work items cost

$$= \sum_{i=1}^n C_i + \sum_{j=1}^m C_j \times 1 + (P_j \times I_j)$$

Step 1 : Customizing work items

Define a breakdown of representative work items which account for more than 95% of cumulative ratio of total project cost, when items listed in the order of high cost

**Add additional phase (Fabrication, Transportation and Installation)*

Step 3 : Calculating weight of modules

Module weight(W_M)

$$W_{PAUS} = W_{ET} + W_{SSU} + W_{PU}$$

$$W_{PARS} = W_{SSR} + W_{PR}$$

Step 5 : Estimating Transportation cost

Transportation cost


$$= W_M \times Dis. \times N_{\$USD / (Km \cdot Ton)}_{Trnas.}$$

Step 7 : Quantifying probability and impact of factors

Define Probability of occurrence and Impact of factors as probabilistic distribution

**Use Bernoulli distribution for probability and Triangular distribution for impact of factors*

02 Break-Even Point



Break Even Units Formula

Break Even Units = $\frac{\text{Fixed Costs}}{SP - VC}$

SP = Selling price per unit
VC = Variable cost per unit

© www.planprojections.com

Fixed Cost

- Factory (1 story 30000FT) \$3,389,900
- Manufacturing Equipment(4) \$5,400,000
- Land Preparation \$1,250
- Maintenance \$2,000
- Renting fee to store the onsite module \$5,000
- Road Closure \$10,000

Variable Cost

Work Item	Description	Conventional construction (UD\$/S.F)	Modular construction (US\$/S.F)
Project duration	–	20 months	16 months
Division 1.1	Indirect cost	\$19.57	\$13.21
Division 1.2	Construction equipment (crane and trucks)	\$1.17	\$5.38
Division 2	Earth working and	\$7.55	\$7.55
Division 4	Masonry	\$5.4	\$3.06
Division 5	Steel structure framing	\$0.96	\$26.44
Division 6	Millwork and carpentry	\$9.97	\$7.97
Division 7	Roofing and siding	\$12.19	\$14.62
Division 8	Doors and windows	\$7.90	\$6.79
Division 9	Interior finishes	\$24.44	\$21.77
Division 10	Specialties	\$1.31	\$1.12
Division 11	Equipment	\$2.69	\$2.23
Division 12	Furnishings	–	–
Division 13	General building items	–	–
Division 15	Mechanical systems	\$26.31	\$23.67
Division 16	Electrical systems	\$13.69	\$12.32
Division 17	Design fee	\$11.79	\$12.00
Total Cost/S.F		\$195.39/S.F	\$173.31/S.F

+

- Transportation \$10.63

03 Calculation

Fixed Cost (\$)	
Factory (1 story 30000SFT)	\$ 338,9900.00
Manufacturing Equipment (4)	\$ 540,000.00
Land Preparation	\$ 1,250.00
Maintenance	\$ 2,000.00
Renting fee to store the onsite modul	\$ 5,000.00
Road Closure	\$ 1,000.00
Total	\$ 3,939,159.00
Variable Cost (\$/S.F.)	
Indirect cost	\$ 13.21
Construction Cost	\$ 160.10
Transportation	\$ 10.63
Total	\$ 183.94 49,120,000
Selling Price	\$ 200.00
Break Even Point (SFT)	2425277.09
Break Even Point (Unit/800SFT)	307

Break Even Units Formula


Break Even Units

=

Fixed Costs

SP – VC

SP = Selling price per unit
 VC = Variable cost per unit



3,939,159


BEP =

3,939,159


200 - 183.94

= 2,425,277 = 307 Units

Break-Even Analysis



04 Risks Affecting Cost



(Nabi et.al., 2021)

Table 1. Modular risk factors

Risk ID	Description
R1	Increased onsite and offsite labor costs
R2	Increased overhead/site preliminary costs
R3	Poor supervision efficiency/costs
R4	Increased transportation costs
R5	High initial (capital) costs
R6	Increased installation and assembly costs
R7	Increased crane and equipment costs
R8	Increased design and engineering costs
R9	Increased cost of materials and modules
R10	Inconsistent cash-flow
R11	Inability to achieve economy of scale
R12	Poor construction activity sequencing/management
R13	Site disruptions and delays
R14	Inclement weather conditions
R15	Long transportation lead times
R16	Increased design and engineering lead times
R17	High shutdown times due to commissioning and testing
R18	Decreased capacity of quality control
R19	Inefficient quality assurance procedures at the manufacturing plant
R20	Rework
R21	Lack of experienced and capable manufacturers/suppliers
R22	Poor aesthetic quality
R23	Geometric variability of modules
R24	Safety accidents/injuries
R25	High workplace congestion
R26	High exposure to hazards
R27	Poor safety planning and communication
R28	Low onsite/offsite productivity
R29	Inability to incorporate modern technologies
R30	Limited capacity to handle and lift equipment
R31	Limited capacity of infrastructure and transportation mode
R32	Poor site attributes and logistics
R33	Shortage of stakeholders' experience
R34	Shortage of skilled and experienced laborers
R35	Incompliance with environmental standards/regulations
R36	High material consumption and waste
R37	Low energy efficiency
R38	Incompliance with green practices
R39	Low level of standardization
R40	Unanticipated field changes
R41	Late design changes
R42	Unsuitability of design for modularization
R43	Low repetitiveness in design
R44	Challenges related to restricted tolerances and interfaces
R45	Lack of adequate collaboration and communication
R46	Cultural resistance to change and innovation
R47	Contractual risks and disputes
R48	Unsuitability of project delivery method
R49	Legal and regulatory challenges
R50	Issues related to project permitting

Table 6. Quantified characteristics of modular risks

ID	Likelihood of occurrence, L		Impact on cost, IC		Cost risk rating, RR_C		
	Mean	SD	Mean	SD	Mean	SD	Rank
R1	2.81	1.36	3.40	1.12	10.25	7.03	17
R2	3.29	1.01	2.79	1.09	9.88	5.92	23
R3	2.48	1.15	2.96	1.34	8.27	6.49	37
R4	3.50	1.15	3.44	1.07	12.63	6.58	6
R5	3.54	1.22	3.27	1.27	12.48	7.70	7
R6	2.85	1.20	3.04	1.11	9.38	6.02	30
R7	2.33	1.19	3.23	1.22	8.23	6.55	38
R8	2.98	1.26	2.88	1.31	9.88	7.02	22
R9	3.00	1.07	3.08	1.27	9.81	5.93	26
R10	2.96	1.32	3.17	1.15	10.31	6.97	15
R11	2.83	1.12	3.54	0.92	10.67	5.81	14
R12	3.13	1.14	3.54	1.13	11.88	6.48	10
R13	2.92	1.03	3.27	1.07	9.81	5.29	25
R14	2.81	1.39	3.23	1.24	10.17	7.52	19
R15	2.79	1.17	3.29	1.15	9.85	6.51	24
R16	3.23	1.24	2.98	1.18	10.13	6.51	20
R17	2.40	1.12	2.90	1.08	7.42	5.20	44
R18	2.25	1.14	2.96	1.35	7.52	5.88	42
R19	2.63	1.04	3.00	1.09	8.40	5.25	36
R20	2.58	0.96	3.48	1.20	9.60	5.92	27
R21	2.75	1.30	3.44	1.15	10.04	6.74	21
R22	2.69	1.06	2.77	1.13	8.17	5.22	39
R23	2.69	1.22	3.08	1.07	8.71	5.78	31
R24	2.35	1.23	3.02	1.47	8.02	6.84	40
R25	2.77	1.28	2.85	1.11	8.65	6.16	32
R26	2.19	1.14	2.38	1.21	6.29	6.12	48
R27	2.25	0.89	2.94	1.33	7.00	4.49	45
R28	2.73	1.05	3.27	1.12	9.52	5.66	28
R29	2.52	1.17	2.94	1.28	8.42	6.13	35
R30	2.17	1.04	3.17	1.15	7.52	5.20	43
R31	2.21	0.99	3.00	1.01	6.88	4.18	46
R32	3.75	0.93	3.46	1.11	13.60	6.58	3
R33	3.13	1.33	3.50	0.99	11.69	7.14	11
R34	3.50	1.15	3.92	1.01	14.50	7.11	1
R35	2.06	1.00	2.83	1.36	6.50	5.34	47
R36	2.44	1.11	2.96	1.13	7.79	5.41	41
R37	1.85	0.85	2.19	0.96	4.65	3.83	50
R38	2.15	1.01	2.35	1.02	5.29	3.68	49
R39	2.35	1.18	3.15	1.35	8.46	6.35	34
R40	3.00	1.17	3.58	1.11	11.13	6.25	12
R41	3.52	1.17	3.67	1.19	13.69	7.36	2
R42	3.33	1.31	3.75	1.10	13.17	7.46	4
R43	2.92	1.01	3.35	1.02	10.31	5.07	16
R44	3.15	0.99	3.63	1.08	12.00	6.34	9
R45	3.23	1.12	3.52	1.05	12.15	6.81	8
R46	3.15	1.30	3.06	1.28	10.92	7.51	13
R47	3.42	1.18	3.44	1.17	12.65	7.05	5
R48	2.58	1.03	3.08	1.13	8.60	5.52	33
R49	3.04	1.03	3.10	1.08	10.19	6.45	18
R50	2.98	1.12	2.92	1.09	9.44	6.43	29

Note: SD = standard deviation.

04 Risk Quantitative Analysis

$$\bar{F} = \sum_{i=1}^{50} W_i \times F_i(\text{RR})$$


where W_i = weight of modular risk i ;

$F_i(\text{RR})$ = value of fitted cumulative distribution function for modular risk i evaluated at point RR specified by the project team.

The cost saving or growth associated with the adoption of modularization in the project is retrieved such that $F(c) = \bar{F}$, where $F(c)$ is the fitted distribution function for the cost performance data.

Major Problems Analyzed

- Shortage of skilled and experienced labors
- Increased Transportation
- Late design changes
- Poor site attributes and logistics
- Unsuitability of design for modularization
- Contractual risks and disputes.



(Nabi et,al., 2021)



Thank you!

Mar 23, 2022



COLUMBIA | CBIPS

Center for Buildings, Infrastructure and Public Space